



DATE: June 23, 1992

TO: District Engineers
District Field Engineers
District Local Government Engineers
Resident/Project Engineers

FROM: Gerald D. Dobie
Engineer of Construction

RE: Construction Instructional Memorandum 1992-15
Progress Schedule for Bituminous Paving Projects

The progress schedule for a bituminous paving project should reflect the time requirement stated in the specifications for placing pavement marking.

Unless superseded, per section 6.29.07 of the 1990 Standard Specifications, "New bituminous wearing surface shall be in place for a period of not less than 14 days prior to application of painted pavement markings and 21 days for polyester resins."

Therefore, the Progress Schedule should not show the pavement markings placed the day after the wearing course is completed.

Engineer of Construction

GDD:JKG:srh

cc: Lansing Staff Engineers
Lansing Staff Technicians
S. Wehrle
S. Olszewski
Local Services Division
Design Division

W. Homrich
M & T
MAPA
MRBA
MCA

Index Subject: Progress Schedule